



PLAN


PIPE GRILLE PLAN FOR PIT LENGTH GREATER THAN 900mm - SHOWN DIAGRAMATIC ONLY




SECTION A



PLAN
PIPE GRILLE FOR PIT DIMENSION 900 x 900mm




FIXING DETAIL - SECTION




BASE PLATE DETAIL - PLAN

NOTES:


- SPAN PIPE GRILLE ACROSS PIT WIDTH.
- LOCATE TYPE (A) PANELS CLOSE TO DRAINAGE PIPE.
- THE NUMBER OF SELECTED TYPE (B) PANELS TO SUIT OVERALL PIT LENGTH.
- ALL PIPE GRILLES ARE NOT TRAFFICABLE. PROVIDE PROTECTION FENCING AROUND THE PIT IN CASE THE PIPE GRILLES ARE HAZARDOUS TO PEDESTRIANS AS PER MELBOURNE WATER STANDARD DRAWING 7251/08/206.
- PROVIDE 600mm CONCRETE APRON AS A HARDSTAND ALL AROUND PIPE GRILL PIT AS PER DRAWING 7251/08/417.
- WORKMANSHIP AND MATERIALS TO COMPLY WITH AS4100, AS/NZS4600, AS/NZS1554.
- PROVIDE STEEL IN ACCORDANCE WITH AS/NZS3678 OR AS/NZS3679 GRADE 250 MINIMUM.
- CARRY OUT WELDING TO AS/NZS1554: ALL INTERFACES BETWEEN STEEL SECTIONS TO BE CONNECTED WITH 6mm CONTINUOUS FILLET WELDS ALL ROUND, BOTH SIDES UNO. WELDS TO BE CATEGORY (SP). ELECTRODES TO BE LOW CARBON CLASSIFICATION E48XX, PRE-APPROVED TO AS/NZS1554.
- ALL PIPE GRILLES AND STEELWORK TO BE HOT DIP GALVANISED. APPLY THE GALVANIZED COATING TO AS/NZS2312.2, TABLE 6.2 SYSTEM HGD900, WITH A NOMINAL THICKNESS OF 125 MICRON OR THE EQUIVALENT MASS OF 900 G/M². REPAIR DAMAGED GALVANIZING IN ACCORDANCE WITH AS/NZS 4680, SECTION 8, BY APPLYING A ZINC-RICH EPOXY COATING USING A SUFFICIENT NUMBER OF APPLICATIONS TO ACHIEVE A TOTAL DFT OF 150 MICRON, (WITHIN 4 HOURS) TO THE PREPARED SURFACE, BY BRUSH OR SPRAY IN ACCORDANCE WITH THE COATING MANUFACTURER'S RECOMMENDATIONS (TYPICALLY TWO COATS ARE REQUIRED TO ACHIEVE THE DFT). EXTEND THE PATCH OF ORGANIC ZINC-RICH COATING A MINIMUM OF 50mm OVER THE UNDAMAGED ZINC COATED SURFACE.
- PROVIDE ADEQUATE VENTING AND DRAINING DURING GALVANIZING TO MEET THE REQUIREMENTS OF THE GALVANISER.
- ABRASIVE BLAST CLEAN TO AS 1627 PART 4 CLASS SA 2½, WITH A MINIMUM SURFACE PROFILE OF 75 MICRONS. GALVANIZE THE STEELWORK IN ACCORDANCE WITH THE REQUIREMENTS OF AS/NZS 4680.
- ALL NUTS, BOLTS AND WASHERS TO BE GALVANIZED TO AS 1214 HOT-DIP GALVANIZED COATINGS ON THREADED FASTENERS (ISO METRIC COARSE THREAD SERIES).
- FOR PIT WIDTH OUTSIDE THE RANGE PROVIDED IN THIS DRAWING, THE PIPE GRILL TO BE DESIGNED BY A QUALIFIED STRUCTURAL ENGINEER.
- MECHANICAL ANCHORS SHALL NOT BE USED IN LIEU OF CHEMICAL ANCHORS.




SECTION B




SECTION C




PANEL - TYPE (A)
HINGED PART




PANEL - TYPE (A)
FIXED PART



TYPICAL PANEL - TYPE (B)
(LAST PANEL WIDTH TO SUIT PIT LENGTH)



HINGE DETAIL



SECURING PLATE DETAIL

<p>H C THIRD REVISION</p> <p>B SECOND REVISION</p> <p>A FIRST REVISION</p>				<p>COMPANY PROJECT OR WO NUMBER DRAWN ENG CHECK PR. MAN APPD DATE</p>				<p>5 6 7 8 9</p>				<p>10 11 12</p>			
<p>REV DESCRIPTION</p>				<p>COMPANY PROJECT OR WO NUMBER DRAWN ENG CHECK PR. MAN APPD DATE</p>				<p>5 6 7 8 9</p>				<p>10 11 12</p>			

COPYRIGHT
Copyright - This document is the property of Melbourne Water. Use or copying of the document in whole or in part, for other than Melbourne Water purposes, without the written permission of Melbourne Water constitutes an infringement of copyright.

Melbourne Water
DRAINAGE STANDARD DRAWINGS

DRAFTER: RD, DESIGNER: GT, DESIGN MANAGER APPROVAL: RM, PROJECT MANAGER APPROVAL: VY

TITLE: **FLAT PIPE GRILLES ARRANGEMENTS**

PROJECT DATUM: MELBOURNE WATER CORPORATION
SCALE: NTS
Original Size: **A1**
7251/08/423
MWC DRAWING NUMBER: 7251/08/423
REV: C