



24 April 2017

Dear Resident,

Williamstown Main Sewer Rehabilitation Project – Stage 2

Stage 2 of the Williamstown Main Sewer Rehabilitation Project is due to start in the week commencing **1 May 2017**. Works for this stage will involve crews setting up a safe working area between two manholes to clean the sewer, reline the sewer using the spiral lining methodology and grouting.

These works will start at the corner of Pasco Street and Railway Place and move progressively along Pasco Street toward Nelson Place. Works along this section are expected to take approximately 4-6 weeks to complete, weather permitting.

Works for this stage will involve accessing each manhole approximately three times to complete the following activities.

- Cleaning – 1 day per manhole.
- Spiral lining – 2 -4 days per manhole
- Grouting – 2 days per manhole.

Timing of works:

Sewer flow trials are being performed this week to determine if works will occur during the day between **7am to 6pm Monday to Friday** and occasionally on Saturday's between 7am to 1:30pm or at night between **8pm to 5am Sunday to Thursday**.

What to expect?

- Some odour when the manhole is first opened
- Some noise from the movement of trucks, machinery and reversing beepers
- Temporary lane/ road closures and changes to the speed limits near work areas
- Please see over page for location of the works.

Pedestrian access around the works will be maintained at all times.



We encourage you to contact us on 1800 813 242 if you have any questions and we thank you for your patience while we undertake these works.

More information

Please email us with your details if you wish to be included on the project emailing list.

email: williamstownsewer@melbournewater.com.au

phone: 1800 813 242

website: www.melbournewater.com.au/williamstownsewer



TTY 13 36 77



**Interpreter Services
13 14 50**